



PLAN NOTES:

1. ELBOW RETURN AIR DUCT INTO PLENUM SPACE. LOUVER OPEN END WITH 1/2" BIRDSCREEN.
2. EF IN CEILING.
3. 18X12 TRANSFER GRILLE.
4. UNIT IS EXISTING AND INSTALLED AS PART OF SHELL DOCUMENTS.
5. 10X6 TRANSFER GRILLE.

GENERAL NOTES:

- A. SIDEWALL DIFFUSERS: TITUS MODEL 300R, OR EQUAL.
- B. RETURN/EXHAUST REGISTERS: TITUS MODEL 50F, OR EQUAL.
- C. CEILING DIFFUSERS: TITUS MODEL TMS, OR EQUAL.
- D. TRANSFER AIR GRILLES: TITUS MODEL 33R, OR EQUAL.
- E. TEST AND BALANCE OF EQUIPMENT REQUIRED BY THIRD PARTY TESTING AGENCY.
- F. COORDINATE WITH SHELL CONTRACTOR FOR SYSTEM START-UP.
- G. CONTRACTOR TO CONFIRM IF SMOKE DETECTOR IS INSTALLED IN SUPPLY AND RETURN AND INSTALL AS REQUIRED.

HVAC
FLOOR PLAN
SCALE: 1/4" = 1'-0"

REV	DATE

PERMIT SET
01-09-09

**RUE 21 AT
SMALL SHOPS
'C & D'
CANTON MARKETPLACE
CANTON, GEORGIA**

SEMBLER
The Sembler Company
1450 South Johnson Ferry Road, Suite 100
Atlanta, GA 30319
Phone: 404-847-1800 Fax: 404-847-1818

MJM
105 Broadway Ave., 4th Floor
Nashville, Tennessee 37201
615-244-8170 Fax: 615-244-8141
www.mjmarch.com

**ENTECH
ENGINEERING INC.**
1711 RAY
AVENUE
NASHVILLE, TN 37203
615-244-8170
www.entechinc.com